

PROJECT: BANK OF INDIA AT WALCHANDNAGAR, PUNE					
CLIENT: ZONAL OFFICE, UNIVERSITY ROAD, PUNE.					
SITE : ADDRESS: WALCHANDNAGAR, DIST PUNE					
<u>A B S T R A C T</u>					
A	INTERIORS & CIVIL WORK				
		Unit	qty	Rate	Amount
1				(Rs.)	(Rs.)
	<u>Flooring (Refer Dwg no B)</u>	sft	1200		
	Providing & laying of 2' x 2' Vitrified Tile flooring of approved make & shade viz. RAK (IMP-OFGY) or EURO (ATHENA) over necessary leveling screed of 1:4 cement mortar (20mm thick) with proper slope wherever required including pointing of the joints with BAL Endura grout, to be laid on existing flooring with fevaimate cement., curing including skirting etc. complete in all respects. Complete.				
2	<u>Facade of Entrance Door- Refer Dwg no.11</u>		175		
	Providing and fixing in position Aluminium composite panel Boxing with PVDF coating & LDPE core laminated Eurobond / Altobond/ Alukbond Exterior Grade 4 mm thick with composite of (0.5mm-3mm-0.5mm) including fabrication for the same with aluminium sections, required hardware, silicon sealent (Dow Corning 789) masking tape, necessary scaffolding etc. as detailed in drawing no.(11) complete in all respects.				
3	<u>False Ceiling (TILED CEILING) Refer Dwg No C)</u>	sft	1200		
	Providing & fixing in position false ceiling in AMF 600 x 600 mm AMF make Feinstratos micro tile VT 15 grid as specified by AMF Co. with suspenders wherever required. and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level,. complete in all respects. All products are to be of AMF tile Company)				
	(Bill to be produced / Certificate from Company at the time of final bill submission for verification)				
3A	<u>SUPPORT FOR FALSE CEILING OF TILE AND GYPSUM CEILING (refer dwg no D)</u>	sft	1200		
	Providing a grid of M.S angle of 75x75x6mm at 3000mm c/c resting on walls as shown on drawing with welding, base plate etc, with one coat of primer etc. Complete Visit site to understand this item in clarity.				

4	<p><u>False Ceiling (Gypsum Board) Refer Dwg No C</u></p> <p>Providing & fixing in position false ceiling in Gypboard 12mm thick for horizontals & verticals fixed over G.I. framework as specified by India Gypsm Co. Ltd. including trap doors for A.C unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects.</p> <p>(Note:- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)</p>	sft	150			
5	<p><u>Painting</u></p> <p>Providing & applying White Plastic Emulsion paint of Asian Paints/ ICI Dulux/ Berger and Sporty Yellow-X104 shade of Royal Luxury Emulsion of Asian Paints in minimum 2 coats including scrapping, opening of existing cracks, filling up of "V" cracks with epoxy expandable putty to required depths, making good weak plastered/ unplastered surfaces with cement plaster wherever required. The painting is to be done on exiting surface provided by landlord.e to receive new paint including cleaning on completion of painting work etc. complete in all respects.</p>	sft	2000			
6	<p><u>Entrance Door</u></p> <p>Providing and fixing Entrance Door (glazed) as per drawing no.11 in Silver Anodised aluminium door section (Jindal make) in top and bottom, glazed with 12 mm thick glass of approved make with etching and frosting. Item to include floor springs, lock, all necessary hardware of Stainless Steel finish as approved by the Project Consultant/ Bank complete in all respects.</p>	sft	35			
7	<p><u>Front Office Counter:</u></p> <p>Providing and fixing in position Front Office Counter 2'-6" wide as per drawing No.(1-A, 1-B, 1-C , 1-D & 15) comprising of the following complete in all respects:-</p> <p>i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼"X1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine finish.</p>	rft	25			

ii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.					
iii) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.					
iv) Glazed partition above working top to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.					
v) 3'-10" high Boxing (10"x10") made with 18 mm thick plywood finished with 1 mm thick laminate including providing and fixing 6 mm thick square frosted glass at a height 3'-2" above finished floor level.					
vi) 1'-9" high Boxing (5"x5") made with 12 mm thick plywood finished with 1 mm thick laminate.					
vii) vertical supports made with 18 mm thick plywood finished with white enamel paint.					
viii) Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.					
ix) Footrest made with T.W. member of size 4" X 1 ½ " finished with french polish.					
x) Drawer units as per drawing shall be provided with multipurpose Godrej locks in Each drawer. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.					

	xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.					
	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with melamine polish for fixing the glass are to be provided.					
8	<u>Cash Counter:</u>	rft	9			
	Providing and fixing in position Cash Counter 2'-9" wide as per drawing No.(2-A, 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the following :					
	i)Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼"X1" Teak Wood moulding finished with melamine polish. Inside edge will be provided with ½ "x1" T.W. beading patti with melamine polish.					
	ii)Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.					
	iii)Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.					
	iv)Glazed partition of 1'-4" height above working top provided with 12mm thick toughened and frosted glass besides non-transparent film from inside fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.					

v)Transaction top shall be provided with 12mm thick toughened glass (partly glazed partly frosted) fixed horizontally with concealed Stainless Steel D bracket. Both exposed edges (inside and outside) shall be moulded and finished in mirror polish.					
vi)Glazed partition having height 1'.0" above the transaction top (in facia) shall be provided with 12 mm thick glass (clear) with cut out of 8"x 4" as per drawing. The edges of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing.					
vii)Glazed partition provided with 12mm thick glass (Clear) above the slit to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. . The exposed edges shall be finished in mirror polish.					
viii) 7'-7" high Boxing (10"x 10") made with 18mm thick plywood as per drawing with 1-6" horizontal extension at the top including providing and fixing 6 mm thick square frosted glass at a height of 5"-11" above Finished Floor level.					
ix) 1'-9" high boxing (5"x 5") made with 12 mm thick plywood finished with 1 mm thick laminate are to be provided.					
x)Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make.					
xi) Footrest made with T.W. member of size 4"X1 ½ " finished with french polish.					
xii) Drawer units as per drawing shall be provided and each drawer should have vertical partitions for keeping the currency notes and multipurpose Godrej locks. Facia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The drawers will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.					
xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling/Telephone wire conduiting.					

	<p>The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary beadings with matching melamine polish for fixing the glass are to be provided as per drawing/ as directed.</p>					
--	--	--	--	--	--	--

9	<p>Solid+Glazed Full Height Partition (in wooden +laminare finish)</p> <p>Providing & fixing in position solid Full Height Partition in frame work including door in 2'x 2' grid (horizontally and vertically) comprising of 2"x 1½" T.W. Section with 6 mm thick plywood on both sides finished with 1 mm thick laminates of approved make and colour as shown in drawing no.17. Item to include 2" x 2" T.W. member for door frame. All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks 6mm thk glass with etched film and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p> <p>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>	sft	410			
10	<p>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p> <p>Providing and fixing in position partly glazed Full Height Partition work as shown in the drawing nos. (3) & (4) including door as shown in the drawing No.(13) in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1½" T.W. Section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings.</p> <p>Item to include 8 mm thick glass with etching and frosting as per design and 2"x 2" T.W. member for door sides and glass sides and T.W. door frame to take 8 mm thick glass with etching and frosting.</p> <p>All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p> <p>(Note: In case of false ceiling, the vertical T.W. members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).</p>					

11	<p>Partly Glazed Partition for Cash Cabins</p> <p>Providing and fixing in position 7'-7" high partly glazed partition for Cash Cabins as per drawing nos. (2-A, 2-B, 2-C, 2-D & 2-E) including door drawing no.(12) in frame work at 2' x 2' grid (horizontally and vertically) comprising of 2" x 1½" T.W. Section and / or as per frame work shown in the drawings with 6mm plywood on both sides finished with 1 mm thick laminates of approved shade and colour as shown in drawings. Item to include 8 mm thick glass with etching and frosting as per design and 2" x 2" T.W. member for door sides and glass sides and T.W. door frame to take 8 mm thick glass with etching and frosting.</p> <p>The door will be provided with T.W. louvers finished in melamine polish of matching laminate colour. The doors are also to be provided with Godrej Night Latch. Two wooden trays are also to be provided as per drawing. Necessary cutouts are to be provided in the glass and the edges of the glass cutouts are to be finished in mirror polish.</p> <p>All exposed T.W. surfaces to be finished in melamine polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant/ Bank complete in all respects.</p>	sft	200			
12	<p>Partly Glazed Low Height Partition</p> <p>Providing and fixing in position partly glazed low height partition (21/2" thick) in frame work with T.W vertical members at 2' c/c and 3 horizontal members at equal distance comprising of 2"x 1½" T.W. Section with 6 mm plywood on both sides finished with 1 mm thick laminates of approved make and shade as shown in drawing no.(14) or (3). Item to include 12 mm thick glass (clear/frosted) to be fixed as shown in drawing. The exposed edges of the glass to be finished in mirror polish. T.W runner should be melamine polished in matching colour of laminate etc complete in all respects.</p>	sft	70			

13	<u>Manager's Table</u>	each	1			
	Providing and fixing in position Manager's Table of size 6'0"x 2'-6" as per drawing no.(6)/ Officer's Table of size 4'-6" x 2'-3" as per drawing no. (5) including Side Storage (Credenza) by using 25mm thick plywood for top and 18 mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4" x 1 ½ " finished with french polish.					
	Side Storage (Credenza) as per drawing shall be provided. Facia of Side Storage (Credenza) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The Side Storage (Credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.					
	All exposed plywood surfaces to be finished with 1mm thk. laminate of approved make & shade, and all exposed edges of table top & ply verticals to have 1" x 1/4" T.W.lipping. All exposed T.W. sections to be melaminated and internal surfaces to have white enamel paint as directed. Item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.					
	<u>Officer's Table</u>					
	Same as above but size 5'0"x 2'0"with side credenza		5			
15	<u>Full height Storage / Low Height Storage/ Back Storage(Credenza)</u>	sft	130			
	Providing and fixing in position Full height Storage / Low Height Storage/ Back Storage(Credenza) as shown in Drg. No.(8), (9) & (10) respectively using Plywood of required thickness finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint as detailed therein.					
	The Storage Units shall be provided with handles (Stainless Steel finish) as per approval of the Project Consultant / Bank.					

	All exposed plywood surfaces to be finished with 1mm thk. laminate of approved make & shade and all exposed edges of plywood to have 1" x 1/4" T.W.lipping. All exposed T.W. sections to be melaminated in matching colour laminate and internal surfaces to have white enamel paint as directed. Item to include all necessary hardware and fittings in Stainless Steel finish, Godrej multi purpose locks including magnetic ball catcher etc., complete in all respects.					
18	VERTICAL BLINDS	sft	130			
	Providing & fixing on site Vertical Blinds of 100mm of vista/mac make of approved shade as directed and channels fixed as per site conditions for measurement window opening shall be considered only.					
20	WRITING DESK (refer no e)	no	1			
	Providing and fixing on site writing desk made in 18mm clear glass with bevelled edge crystal polish supported on panelling behind with S.S studs the front shall have 10mm thk glass fixed with S.S studs and caps for holding slips/challans. including dust box shown below. As shown on drawing and directed by Architect.All surfaces are to be finished in laminate Complete.					
22	PANELLING	sft	60			
	Providing & fixing on site wall panelling in 6mm ply finished with 1mm laminate. As per design shown and directed by Architect with edge 8mm thk agrowoob. lipping finished in polish etc. The panelling shall have gap of 35mm from wall to be provided by 35mmx35mm thk hardwood laminate treated with anti termite for levelling surface and fixed at 600mmx600mm horizontal and vertical (for concealing conduits pipe) complete.					

