

Tender sending format	
Title of the tender	Civil/Interior/Electrical Furnishing for our Thanegaon Branch
Category	Empanelled
Zone	Nagpur I Zone
Item	Civil/Interior/Electrical Work
Tender Date	12/6/2010
Last Date of submission	23/6/2010
Display from	12/6/2010
Display upto	23/6/2010
Description	As per enclosed attachment
PDF file Names	Webtender1(1).pdf

**NAME OF THE PROJECT: BANK OF INDIA, THANEGAON.
CIVIL WORK.**

Sr.No.	DISCRIPTION	QUNTITY	RATE	AMOUNT
01	Providing & fixing Channel gate (collapsible steel gates) in two leaves with channel pickets, pivoted flat bars, including Top & bottom guides, rollers, locking arrangement & one coat of red primer.	70 Sq ft		
02	Providing & fixing Polycarbonate Sheet 5 mm thick over the Structure for Entrance canopy of size 10'0" X 10'0" with vertical pipes & Horizontal pipes 1.6" o with proper fixing arrangements & per the drawing & instructions on site.	100 Sq ft		
06	Dismantling of wall below R.C.C Staircase & putting the 'T' section as per the instruction of the structural designer & making it all right by replicating etc. complete.	LUMSUM		
07	Providing a 3'0" X 7'0" opening inside a wall of advances, providing a wooden frame 4.6" X 2." & single shutter co hid flush door 35 mm thick covered with 1 mm laminate including all fittings & fixtures as dissected by Architect.	1 No's		
08	Providing & replacing the existing toilet door shutters with sintex P.V.C shutters with all fitting & fixtures etc complete.	2 No's		
09	Removing the existing door/wall in the Staircase room & plastering the same to bring it to the original position.	2 No's		
10	Providing & fixing verified tiles over the existing floor in chemical solution but maintaining the proper line & level with proper joint filling etc complete.	1250 Sq ft		
11	Providing & coloring the internal area by scrapping the old color, applying 2 coats of primer, 3 coat of putty & 3 coats of acrylic Emulsion (velvet Touch or equivalent) till the satisfaction of Architect.	7000sq ft		
		TOTAL AMOUNT		

Seal & Signature of Contractor

Date:

**NAME OF WORK : FURNITURE WORK FOR BANK OF INDIA,
THANEGAON BR.**

Sr No	Description	Qty.	Rate Rs.	Per	Amount
1	MAIN ENTERANCE GATE FULLY GLAZED Providing & fixing fully glazed powder coated Aluminium entrance door with side full glazed aluminium fixed partition, at Entrance as per design, drawing and as directed made out of standard Aluminium sections(Jindal make) Outer frame of 100x44x1.5 mm thick, vertical Styles of 83x44x1.5 mm thick, bottom 144x44 1.5mm thick & top of 44x100x1.5 mm thick, and middle rail of 83x44x1.5 mm thick, with mm thick float glass (modi/Asahi/St. Gobain coat) for door shutter and fixed Partition with necessary Etching work beveling, etc. complete fixed on floor spring of Ozone/Derma/ Godrej make(I.S.I mark, Heavy duty, Item taken separately).The shutters shall have Night latch of Godrej make/mortise lock, Aluminum Tower Bolt 150mm 150 mm long, Aluminum Handle 150 mm on both sides of approved make, Al. Door Stopper etc. with erection, fixing, finishing etc. complete and as directed by Architect. The work includes anodizing of Aluminum Sections in approved shade & colour as directed.	24.5		Sq Ft	
2	F.O.C Providing and fixing in position Front Office Counter 2'-6" wide comprising of the following complete in all respects.	8		R Ft.	
	i) Working top made with 25mm thick plywood finished with 1mm thick laminate. Outside edge of the working top shall be provided with 1¼ x 1" Teak Wood molding finished with melamine polish. Inside edge will be provided with ½" x 1" T.W. beading Patti with melamine finish.				
	ii)Vertical fascia (Apron) made with 18mm thick plywood finished with 1mm thick laminate with 1mm thick groove at the joint of laminates of two different shades.				
	iii)Vertical drop (horizontal band) shall be provided on the fascia below the working top made with 18mm thick plywood' finished with 1mm thick laminate with provision for concealed light, 1 mm thick groove shall be provided at the joint of two different shades of laminate.				
	iv) Glazed partition above working top to be provided with 12mm thick clear glass cut to the standard shape fixed to partition as per fixing details and to boxing with concealed S. S. finished D brackets as shown in the drawing. The exposed edges of the glass shall be finished in mirror polish.				
	v) 3'-10" high Boxing (10"x10") made with 18 mm thick plywood finished with 1 mm thick laminate including providing and fixing 6 mm thick square frosted glass at a height 3'-2" above finished floor-level.				
	vi) 1'-9" high Boxing (5"x5") made with 12 mm thick plywood finished with 1 mm thick laminate.				
	vii) Vertical supports made with 18 mm thick plywood finished with white enamel paint.				
	viii) Telescopic CPU Stand/ readymade Keyboard j tray shall be provided of approved model and make.				
	ix) Footrest made with T.W. member of size 4" x ¼ " finished with French polish.				
	x) Drawer units as per drawing shall be provided with multipurpose Godrej locks in Each drawer. Fascia of drawer unit shall be finished with 1mm thick laminate and all other sides shall be finished with white enamel paint. The draws-'s will be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank.				
	xi) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conducting and at the bottom for the LAN cabling/Telephone wire conducting.				
	The item to include all necessary hardware and fittings in Stainless Steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop and also in the 10"x10" boxing as shown in the drawing. Necessary headings with melamine polish for fixing the glass are to be provided. fixing the glass are to be provided.				
3	CASH COUNTERS Providing & Fixing partly glazed partly paneled T.W. Door to cash at required position made out of C.P. Teak wood framework of 75x35mm @ 375mm c/c both ways with 6mm thick ply of MR grade of ISI mark confirming to IS-303 (Narrottam/ Ecotech/ Amul /Mayor/ Rama ply TREND/ Green/ Kit ply) on both side & finished with 1.00mm thick laminate (Vie Sundeck/ Kirtland/ Merino am/ Century/ Amelia/ Botanical or Equivalent) as directed vibrate architect. The upper portion of the stature shall have 5mm thick glass panel above 900mm or as directed from floor level with necessary etching & with T.W Beading of size 25x12mm. The Godrej make / Mo0rties Lock/ Aldrops as per requirement, Brass Tower bolt 150mm long, Brass Handle 100mm, Door stopper with erection, finishing etc. complete and	8		R Ft.	

Date:

Seal and Signature of Contractor

NAME OF WORK: ELECTRICAL WORKS FOR BANK OF INDIA, THANEGAON, DIST.
NAGPUR

Item No.	Description	Qty.	Rate	Per	Amount
	REVENUE ELECTRICAL				
1	Providing & fixing Bus Bar of approved make and quality of 100 Amp. With endoser in panel board including aH Lux, Cable crimping, fixing and inclusive of all connections etc. complete.	1.00		No.	
2	Providing & laying & Termination of 35 sq.mm.X 31/2 Core Armoured Aluminium cable of I.S.I, make (Aluminium Conductor Heavy Duty 1100 V Grade Cables) with 2 run of 8 SWG G.I. earthing wire connected with suitable Glanel & Lugs from Bus Bar / Meter panel board to Main electrical Distribution Board overhead open fixed with saddle & screws complete (Supreme/Polycab make only)	30.00		Rmt	
4	Supplying and erecting approved make 2x40 Watt fluo fitting recess / surface mounting mirror optic type made from CRCA sheet not less than 0.7 mm thickness white on reflector side and gray on other surface complete with one 40 watt copper VPIT ballast, lock type tube holders, starter, starter holder and condenser duly wired up suitable for 250 V supply and erected with flexible twin core wire 24/0.2mm and with necessary materials and marking Sr. No. and date of erection. (Philips / Crompton / Bajaj make)	32		Rft.	
5	Providing & fixing call bell points wiring by using 1 sq.mm x 2 wire along with dingdong bell and 2 mm thk 25 mm dia conduits pipe concealed/ open rigid PVC truncking, as directed, including bend, tee of Precision make only.	1		No.	
6	Providing and fixing of Twin Anchor Bolt for ceiling fan including fixing etc. complete.	13		No.	
7	GENERAL WIRING FOR LIGHTS/FAN /PLUG POINTS etc. Providing & fixing Light points wiring by using 1.5sq.mm. X 2 wire in P.V.C. 2Mm thick. 25 mm dia conduits pipes accessories/conduit pipe/open rigid P.V.C. truncking, as directed, including bend, tee of Precision make only (Polycab make) wherever required as per the directions of the Architect.	60		No.	
8	Providing and fixing of 6A plug points by using earthing wire and 2 mm thick. 25 mm dia conduits pipe concealed / open rigid PVC truncking, as directed, including bend, tee of precision make with Anchor Roma make (wire Polycab make) wherever required as per the directions of the Architect	08		No.	
9	Providing and fixing of sub main wiring by using 2.5 sq.mm x 2wires + 1.5 sq.mm x 1 wire as an earth along with 2 mm thick 25 mm dia PVC pipe concealed/ open rigid PVC truncking, as directed, including bend , tee of Precision/Vasan's make only from main distribution to switch board as per load distribution (Polycab make).	550		Rft.	

10	Providing & fixing sub main wiring by using 1.5 x 2 wires +1.5 Sq.mm x 1 wire as an earth along with 2 mm thick 25 mm dia PVC pipe concealed/ open rigid PVC trucking, as directed including bend, tee of Vasan's/ Precision make only from switch board to light points (Polycab make)	800		Rft.	
11	Providing & fixing circuit wiring for inverter from lighting switch board using 1.5 sq.mm wire.	300		Rft.	
12	Telephone points: Providing & fixing of telephone point with 4 pair telephone cable with 2mm thick 25 mm dia concealed/ open rigid PVC trucking, as directed.	3		No.	
13	Providing & fixing of running circuits wiring or telephone point from EPBAX to telephone points with 4 pair telephone cable with 2 mm thick 25 mm dia concealed/open rigid PVC trucking, as directed complete.	150		Rft.	
14	Dedicated Earthing by using 600 mm x 3 mm thick. Copper plate with reveting and nut bolting 25 x 3 mm copper strip 10 mtr from earth pit to wall surface and 50 kg Charcoal and excavation of hard concrete surface refilling of soil and plaster. Earthing must have waterproofing arrangement with funnel and stop cock, complete .	1.00		No.	
15	1) From earthing to main distribution board copper strip running)	15		Rmt	
17	Supplying & erecting triple pole metal / iron clad HRC fuel switch 415/500 V 100 A with neutral link (Ashoka make)	01		No.	
LIGHTING FIXTURES					
1.	Providing & fixing RCCB 100 Amp. 4 Pole , with Enclosure on Panel board including installation, wiring, crimping etc Complete. (Legrand (MDS) make only.	1.00		No.	
3.	For Electrical circuit: Providing & fixing 4 way TPN Distribution box MDS (Legrand) make.	1.00		No.	
4.	Lighting circuit Wiring: Providing & fixing 10A/32A/ SPMCB for electrical circuits single pole including crimping, wiring, installation for electrical output along with 'MDS' (Legrand) for I/P circuits with lable holder etc. complete.	10		No.	
8.	Providing Ceiling Fans of approved make (Bajaj Regal Gold) of 1200mm/920mm sweep with electronic regulator assembly.	13		Nos.	
9.	Running circuit from main switch to DB 4 Sq mm wire X 4 wires. + 2.5 Sq mm wire for earth.	95		Rft.	
10.	A.C Point wiring using 4 Sq mm x 2 wire + 2.5 Sq mm wire for earth. With providing Ac box.	2.00		Nos.	

Date:

Contractor

Seal and Signature of